



### 1. INPUT POWER:

# **Input Line Voltage Range**

100VAC  $\sim$  240VAC, 50/60Hz , 8 Amp RMS max.

# 2. OUTPUT VOLTAGE PERFORMANCE:

### 2.1 Tube Voltage Operational Range

40kV ~ 160kV

### 2.2 kV Accuracy

The high voltage measured at the X-ray tube shall be within +/-2% of the selected value.

### 2.3 kV Ripple



The low frequency ripple (<1kHz) shall be within 1% (P-P) of the total kV.

### 2.4 Voltage Regulation

Better than 1% for +/-10% of nominal input line voltage.

### 2.5 Voltage Regulator Precision

0.5kV

#### 2.6 kV/mA Rise time

The kV and mA rise time may be controlled digitally. Minimum ramp-up time is 200mS.

### 3. OUTPUT CURRENT (mA) PERFORMANCE:

#### 3.1 Tube Current

1.0mA~3.0mA @ 160kV, 500W maximum.

### 3.2 mA Regulation

Better then 1% between 80~160kV, 1.0mA to 3.0mA.

### 4. PROTECTION CIRCUITRY:

#### **4.1 Current Protection**

The OVER mA trip point is set at 50% over selected output current value.

### 4.2 Voltage Protection

The OVER kV trip point is set at 25% over selected output current value.

### 4.3 Over temperature protection (Option)

Over temperature interlock point shall be set 65°C as measured from tank body.

### 5. FILAMENT POWER AND FOCAL SPOT:

5.1 Filament Current Output: 3.2A

**5.2 Filament Voltage Output:** 3.5V

**5.3 Focal Spot Size:** 1.2mm × 0.8mm







### 6. RADIATION SAFETY REQUIREMENTS:

X-ray leakage is less than 0.5mR/hr measured 5cm from the external surface at 1.0mA emission current and 150kV, with output window blocked.

#### 7. OPERATION SPECIFICATIONS:

### 7.1 Operation Mode

Continuous or pulsing operation.

### 7.2 Seasoning

Digitally controlled seasoning available (digital board required).

7.3 Operating Ambient Temperature: 0°C~40°C

7.4 Storage Temperature: -20°C~60°C

**7.5 Humidity:** ≤85%, no condensation

#### 7.6 Dimensions

X-ray generator head: 860mm×240mm×230mm; Weight: 75kg

Controller box: 400mm×400mm×120mm; eight: 5kg

### 7.7 X-ray Beam Filtration

2mm Glass + 12mm Oil (equivalent) + 3mm PEEK

### 7.8 X-ray Beam Geometry

Fan beam:  $80^{\circ}\pm2^{\circ}$   $(40^{\circ}+40^{\circ}) \times 10^{\circ}\pm1^{\circ}$   $(5^{\circ}+5^{\circ})$ 

### 7.9 Cooling Mechanism

Head inside: Oil convection External: Forced oil cooling.

#### 8. COMPONENT

### 8.1 X-ray Generator Head

### 8.2 Controller Box





Including digital and analog control boards and one cable from X-ray generator head to the controller box (length 1.6 meter).

### 8.3 Collimator

Optional to customer request.

### 9. INTERFACE SPECIFICATION

### 9.1 AC Power Connector


AC Power input (PL5), Amp CPC connector is used for AC input.

Connector: Amp PN. 206036-2		
Pin	Contact (Amp PN)	Description
1	66261-2	LINE (Hot, Fire)
2	66261-2	NEUTRAL (Zero)
3	66262-2	GND

### 9.2 Control Signal Connector

Control Signal Connector (PL4), This connector caries signals for X-ray ON, and interlocks mains power cutout. It uses a Amp CPC connector with AMP contact sockets.

Connector: Amp PN.206705-1			
Pin	Contact (Amp PN)	Description	
1	66565-4	X-ray On- Collector	
2	66565-4	X-ray On return - Emitter	
3	66565-4	Enable In	
4	66565-4	Enable Return	
5	66565-4		







6	66565-4	Spare Port
7	66565-4	Spare Port
8	66565-4	Interlock In
9	66565-4	GND (Interlock Return)

#### 9.3 RS232 Connector

RS232 Connector PL1 (Digital Signals Interface):

RS232: PL1-2 (RXD)

RS232: PL1-3 (TXD)

RS232: PL1-5 (GND)

### 9.4 GND Connector PL6

Ground stud provided on chassis

### 9.5 X-ray Generator Power Connector PL2

PL2-1, PL2-3: Transmission power to the filament

PL2-4, PL2-5: Transmission power to the High voltage transformers

### 9.6 X-ray Generator Signal Connector PL3

PL3-1: - kV feedback signal

PL3-2: +kV feedback signal

PL3-3: kV\_GND

PL3-5: mA\_GND

PL3-6: +mA feedback signal

PL3-7: S\_GND

PL3-8: - mA feedback signal

#### 9.7 Indicator information

POWER: When power-on, the bright lights

INTERLOCK: When interlocked conditions set up, bright lights





X-RAY ON: When the X-ray emission, bright lights

FAULT: When the fault occurred, the bright lights

### 9.8 Analog Signals Interface

- Tube voltage input signal (H9-PIN3): 0~5 VDC analog signal.
- Tube voltage output signal (H9-PIN1): 0~5 VDC analog signal.
- Tube current input signal (H9-PIN4): 0~5 VDC analog signal.
- Tube current output signal (H9-PIN2): 0~5 VDC analog signal.
- X-ray On/OFF signal (PL4-1, PL4-2):

Parameter	Value
Open circuit voltage	30V
Max Continuous current	1mA

• Interlock Input signal (PL4-8, PL4-9):

Parameter	Value
Open circuit voltage	24V
Minimum closed circuit continuous current	15mA
Nominal closed circuit continuous current	100mA
Maximum closed circuit continuous current	150mA
Inrush current	< 1A

• Enable Inputs Signal (PL4-3, PL4-4):

Parameter	Value
Input Voltage (asserted)	
Asserted	> 20V (nominal 24V)
Not Asserted	< 5VDC
Nominal Current	10mA

# Reliable. Efficient. Proven!





Max Current	20mA

• X-ray READY signal: kV>80kV and mA>1.0mA

	LD2	H10-4 (READY signal)
X-ray READY	Illuminated	Low level
X-ray NOT READY	Dimm	High level

• The current high signal (mA OVER): The mA OVER trip point is set at 50% over current fault signal.

	LD4	H10-9 (mA OVER signal)
mA OVER range	Illuminated	Low level
mA Normal	Dimm	High level

• The voltage high signal (kV OVER): The kV OVER trip point is set at 25% over voltage fault signal.

	LD3	H10-7 (kV OVER signal)
kV OVER range	Illuminated	Low level
kV Normal	Dimm	High level

• Fault signal (H10-PIN5):

	H10-5 (ERROR signal)
Error	Low level
Normal	High level

• Signal Ground:

(H10-3, H10-6, H9-5)

### 9.9 Communication Interface (RS232)

RS232 connector is standard 9-Pin D-sub male connector.

Baud Rate Setting: 9600

Parity: Even



Data Bits: 8

Stop Bits: 1